

- The scheduling of any water shut downs shall be as per Item 801 of the current CCMS. Time and duration of all shut downs shall be determined by Division of Water. The Contractor shall notify all water customers effected by the proposed work at least 24 hours in advance of the scheduled shut down.
- 2. All bends shall be secured by retaining glands, rodding or other methods as approved by the Engineer to restore the water main to service as soon as possible. For water lines 16" and under concrete backing shall then be provided in accordance with Standard Detail L-6310 for over bends and L-6311 for sag bends.
- 3. Existing Water Lines 20" and greater must have prior approval of DOW to lower under a proposed utility. Approval will only be given under special circumstances and contingent upon the Contractor submitting a designed drawing, stamped by a Professional Engineer, detailing how the lowered water line will be restrained to the existing water main.
- 4. The relocated lines shall be laid to the new line and grade, tested and disinfected prior to shut down of existing main and connection of the relocated lines to the existing main.
- 5. All water lines shall be disinfected by swabbing with a 5 per cent Hypochlorite solution in accordance with the applicable sections of A.W.W.A. C-601.

CITY OF COLUMBUS
DEPARTMENT OF PUBLIC UTILITIES
DIVISION OF WATER

APPROVED:

C. Westerfield

ADMINISTRATOR

DATE

STANDARD DETAIL

TYPICAL WATER LINE LOWERING

