

500 STRUCTURES

ITEM 504 - SHEET PILING LEFT IN PLACE

- 504.01 Description**
- 504.02 Materials**
- 504.03 Driving**
- 504.04 Method of Measurement**
- 504.05 Basis of Payment**

504.01 Description. This work shall consist of furnishing and driving of steel sheet piling to be left in place including the furnishing and installing of any specified anchors or other attachments to structures.

504.02 Materials. New sheet piling shall conform to the requirements of Section 711.03. Used sheet piling in good condition which meets project requirements may be used if inspected and approved by the Engineer.

504.03 Driving. Steel sheet piling shall be driven to the penetration of bearing capacity called for on the plans.

504.04 Method of Measurement. The quantity shall be the number of square feet (square meter) measured in the plane of the face of sheeting, complete in place as required by the plans.

504.05 Basis of Payment. Payment will be made at the contract unit price for:

Item	Unit	Description
504	Square Feet (Square Meter)	Steel Sheet Piling Left in Place (Minimum Section Modulus of ____ Inches ³ Per Foot (mm ³ /m) of Wall)