CITY OF COLUMBUS
PUBLIC SERVICE DEPARTMENT
TRANSPORTATION DIVISION

SUPPLEMENTAL SPECIFICATION 1550
CURB RAMPS

August 28, 2002

1550.01	**Description**
1550.02	**Excavation and Forms**
1550.03	**Placing and Finishing**
1550.04	**Curing**
1550.05	**Method of Measurement**
1550.06	**Basis of Payment**

1550.01 Description. This work shall consist of constructing curb ramps, including ramps, flares, landings, and sidewalk transitions, in accordance with lines, grades, and dimensions shown on the plans or established by the engineer. Except as noted, all work for this item shall conform to item 451.

1550.02 Excavation and forms. Excavation and forms shall conform to Section 608.03 (a) and (b).

1550.03 Placing and Finishing. Placing and finishing shall conform to Section 608.03 (c).

1550.04 Curing. Concrete shall be cured in accordance with Section 451.10.

1550.05 Method of Measurement. Curb ramps in concrete sidewalk will be measured and paid as both square feet of sidewalk and as the number of curb ramps complete. The unit payment for each curb ramp shall include the cost of any additional materials, grading, forming and finishing not included in the square unit item for sidewalk.

This item shall include furnishing, placing, preserving construction layout, including field painted markings, or other controls, in accordance with the contract plans and proposal for the construction of various elements of the project.

1550.06 Basis of Payment. The accepted quantities of specific items of curb ramps will be paid for at the contract prices designated for each of the pay items listed. Excavation, backfill, expansion joint material and other related miscellaneous items will not be paid for separately. The cost thereof shall be included in the cost of the walk or curb ramp which they are a part of. (However, work to lower curb ramp landing areas or alter slopes will be paid under Item 203.)

Item	Unit	Description
1550	Square Foot	Concrete Walk, 4-inch
1550	Square Foot	Concrete Walk, 8-inch
1550	Each	Curb Ramp, Cost to Finish